



Phone: (832) 650-6500
Email: help@arcsvcs.com
Web: arcsvcs.com
LICENSED & INSURED

WATER DAMAGE REPAIR ESTIMATE — MASTER BATHROOM

Estimate #: ARC-2026-0806-001

DATE
August 6, 2026

PREPARED FOR
David Minitier

PROPERTY LOCATION
3231 Appalachian Trl
Kingwood, TX 77345

PROJECT SCOPE: MASTER BATHROOM — WATER DAMAGE REPAIR

Repair of the water-damaged wall and baseboard at the vanity wall of the master bathroom. The affected material is removed, the wall cavity is dried and treated, and the wall is rebuilt and refinished. Each stage of the work is broken out below. Two options are presented. Plumbing repair, tile work, flooring, and third-party testing are not included.

SCOPE OF WORK & PRICING

Scope of Work	OPTION A Repair affected area	OPTION B Full finish, no patch
Site Setup, Protection & Removal of Damaged Material Protect the surrounding area and fixtures, open the wall, remove and dispose of the water-damaged material, and treat the exposed area.	\$177.59	\$177.59
Structural Drying & Daily Monitoring Professional drying equipment placed on the wall cavity, with a technician on site to monitor and document progress until the wall reaches a dry standard.	\$407.65	\$407.65
Vanities Removed & Reset Both vanities carefully detached and reset afterward, so the wall and baseboard behind them can be finished properly rather than cut around.	<i>Not included</i>	\$842.08
Wall Rebuilt & Textured New drywall hung, taped, floated, and textured to match the existing wall finish.	\$611.16	\$611.16
Baseboard Removed & Reset Option A covers the affected section of baseboard. Option B covers all baseboard in the bathroom.	\$7.44	\$69.44
Priming & Painting Option A primes and paints the repaired area. Option B repaints the walls and baseboard wall to wall for a uniform finish. A painter's minimum charge applies either way, so the full repaint adds very little.	\$316.08	\$385.24
Final Detailed Cleaning Detailed cleaning of the bathroom once the work is complete.	<i>Not included</i>	\$46.80
Line Item Subtotal	\$1,519.92	\$2,539.96
Est. Material Sales Tax (8.25%, materials only)	\$50.16	\$83.82
ESTIMATED TOTAL	\$1,570.08	\$2,623.78

Note: Labor to repair, remodel, or restore residential property is not subject to Texas sales tax; only materials are taxed. The material tax shown is an estimate and the exact amount will be reflected on your final invoice. This estimate is based on visible conditions at the time of inspection and is subject to change once the wall is opened; any additional conditions found will be priced by written change order and approved by you before that work proceeds. Please note the damaged wall backs the vanity plumbing. The source of the moisture is not included in this estimate and should be verified and repaired by a licensed plumber; without that repair the damage can return. A 3.5% surcharge applies to credit card payments; no surcharge on check, ACH, or debit.

NEXT STEPS

STEP 1: APPROVE

Let us know which option you would like to move forward with and we will confirm your project scope.

STEP 2: SCHEDULE

We will coordinate a start date that works for you and confirm it in writing before we arrive.

STEP 3: CLEAR AREA

Please clear the vanity countertops and remove personal items from the bathroom before our crew arrives.