



Phone: (832) 650-6500
Email: help@arcsvcs.com
Web: arcsvcs.com
LICENSED & INSURED

WATER DAMAGE REPAIR ESTIMATE — MASTER BATHROOM

Estimate #: ARC-2026-0806-001

DATE
August 6, 2026

PREPARED FOR
Homeowner

PROPERTY LOCATION
3231 Appalachian Trl
Kingwood, TX 77345

PROJECT SCOPE: MASTER BATHROOM — WATER DAMAGE REPAIR

Repair of water-damaged wall and baseboard at the vanity wall of the master bathroom. The affected material is removed, the wall cavity is dried and treated, and the wall is rebuilt and refinished. Two options are presented below. Plumbing repair, tile work, flooring, and third-party testing are not included.

WHAT'S INCLUDED

- ✓ Removal of water-damaged wall material
- ✓ Anti-microbial treatment of the affected area
- ✓ Professional drying of the wall cavity
- ✓ Daily monitoring to a documented dry standard
- ✓ Wall rebuilt, textured, and refinished
- ✓ Baseboard removed and reset
- ✓ Debris removal and disposal
- ✓ Final cleanup of the work area

SCOPE OF WORK & PRICING

Description	OPTION A Repair affected area	OPTION B Full finish, no patch
Water Mitigation & Dry-Out	\$585.24	\$585.24
Remove the water-damaged wall material, treat the area, and dry the wall cavity with professional drying equipment until it reaches a documented dry standard.		
Repairs & Finish	\$934.68	\$1,954.72
Option A — rebuild and refinish the repaired section only, and reset the affected baseboard. Option B — both vanities carefully removed and reset for full access, all baseboard removed and reset, and the bathroom walls and baseboard repainted wall-to-wall for a uniform finish rather than a patch.		
Line Item Subtotal	\$1,519.92	\$2,539.96
Est. Material Sales Tax (8.25%, materials only)	\$50.16	\$83.82
ESTIMATED TOTAL	\$1,570.08	\$2,623.78

Note: Labor to repair, remodel, or restore residential property is not subject to Texas sales tax; only materials are taxed. The material tax shown is an estimate and the exact amount will be reflected on your final invoice. This estimate is based on visible conditions at the time of inspection and is subject to change once the wall is opened; any additional conditions found will be priced by written change order and approved by you before that work proceeds. Please note the damaged wall backs the vanity plumbing. The source of the moisture is not included in this estimate and should be verified and repaired by a licensed plumber; without that repair the damage can return. A 3.5% surcharge applies to credit card payments; no surcharge on check, ACH, or debit.

NEXT STEPS

STEP 1: APPROVE

Let us know which option you would like to move forward with and we will confirm your project scope.

STEP 2: SCHEDULE

We will coordinate a start date that works for you and confirm it in writing before we arrive.

STEP 3: CLEAR AREA

Please clear the vanity countertops and remove personal items from the bathroom before our crew arrives.